Second floor 30.00L

BRUHATH BANGALORE MAHANAGARA PALIKE

Rajarajeshwari Nagara Division

SCHEDULE-B

Name of Work : Construction of Second floor office for ARO (Yeshwanthpur) at JP Park Swimming Pool Parking area in ward no 17.

Agency			M/s Vrushabhadri Constructions		
Sl No.	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
1	38.85	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc , including smooth finish in CM 1:3, with all lead and lift etc , complete (exculsive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-30 (Cement-360 Kg/cum) and as directed by the Engineer in Charge of the work.	Cum	7060.00	Rupees Seven Thousand Only
2	54.39	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Fe 415 and as directed by the Engineer in Charge of the work.	Qtl	7640.00	Rupees Seven Thousand Six Hundred Forty Only
3	9.66	KSRB 4.2.10 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs, with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 and as directed by the Engineer in Charge of the work.	Sqm	433.00	Rupees Four Hundred Thirty Three Only
4	92.23	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc , for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 and as directed by the Engineer in Charge of the work.	Sqm	389.00	Rupees Three Hundred Eighty Nine Only
5	121.02	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc , and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 and as directed by the Engineer in Charge of the work.	Sqm	407.00	Rupees Four Hundred Seven Only
6	65.39	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2and as directed by the Engineer in Charge of the work.	Sqm	294.00	Rupees Two Hundred Ninety Four Only
7	32.06	KSRB 4-6.11 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 and as directed by the Engineer in Charge of the work.	Sqm	525.00	Rupees Five Hundred Twenty Five Only
8	12.81	KSRB 4-6.10 :Providing and removing centering, shuttering, strutting, propping etc , for chajjas, corbels etc , including edges including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 and as directed by the Engineer in Charge of the work.	Sqm	297.00	Rupees Two Hundred Ninety Seven Only
9	144.15	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. and as directed by the Engineer in Charge of the work.	Sqm	953.00	Rupees Nine Hundred Fifty Three Only
10	3.63	KSRB 5-15 : Providing and constructing non-load bearing wall with cement concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 (Jamb, closer blocks) with blocks of size 40x10x20cms. (lxbxh) conforming to I.S : 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. and as directed by the Engineer in Charge of the work.	Sqm	683.00	Rupees Six Hundred Eighty Three Only
11	7.46	KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 Colour glazed tiles 30x45 cms 6mm thick with border of size 30x10 cms and as directed by the Engineer in Charge of the work.	Sqm	1324.00	Rupees One Thousand Three Hundred Twenty Four Only
12	116.64	Providing and laying flooring using prepolished, water cut/ gang saw 19mm thick granite laid over existing floor in CM 1:4 at 20mm thick (average) and pointed with white / gey pigment etc., complete using Black granite and as directed by the Engineer in Charge of the work.	Sqm	2549.00	Rupees Two Thousand Five Hundred Forty Nine Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

Scanned by CamScanner

	Qty	Item Description	Unit	Rate	
				In Figures	In Words
		3	4	5	6
	1.92	KSRB 14.14-5: Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. Specification No. KBS (for Ceramic Tiles of size 30 x 30 cms) and as directed by the Engineer in Charge of the work.	Sqm	984.00	Rupees Nine Hundred Eighty Four Only
14	19.69	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, curing etc ,complete and as directed by the Engineer in Charge of the work.	Sqm	4157.00	Rupees Four Thousand One Hundred Fifty Seven Only
15	124.83	KSRB 15.3.1Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. and as directed by the Engineer in Charge of the work.	Sqm	169.00	Rupees One Hundred Sixty Nine Only
16	103.25	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Pg :123 - 1:15.21 of KPWD S.R 2013-14)	Sqm	171.00	Rupees One Hundred Seventy One Only
17	124.83	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. with primer and as directed by the Engineer in Charge of the work.	Sqm	83.00	Rupees Eighty Three Only
18	103.25	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. with primer (For Ceiling) and as directed by the Engineer in Charge of the work.	Sqm	91.00	Rupees Ninety One Only
19	724.37	KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. and as directed by the Engineer in Charge of the work.	Sqm	235.00	Rupees Two Hundred Thirty Five Only
20	724.37	KSRB15-4.7 Extra for providing and mixing waterproofing compound in cement plaster for brick masonry work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:4, 20mm thick cost of materials complete as per specifications and as directed by the Engineer in Charge of the work.	Sqm	11.00	Rupees Eleven Only
21	89.85	KSRB 15.8.1 Providing and fixing plaster mesh 100mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment) and as directed by the Engineer in Charge of the work.	Rmtr	31.00	Rupees Thirty One Only
22	724.37	Providing and finishing external walls in two coats over one coat of primer with antifungal paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and as directed by the Engineer in Charge of the work.	Sqm	141.00	Rupees One Hundred Forty One Only
23	0.68	KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 and as directed by the Engineer in Charge of the work.	Cum	110729.00	Rupees One Lakh Ten Thousand Seven Hundred Twenty Nine Only
24	25.89	KSRB 9.5-2 : Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 and as directed by the Engineer in Charge of the work.	Sqm	4733.00	Rupees Four Thousand Seven Hundred Thirty Three Only
25	1.08	KSRB 9-26.1 : Providing and fixing in position fully glazed shutters for ventilators side hung or central pivoted with Honne wood styles and rails of 25mm. thick, 50mm wide and central divider of 25mm. wide, 3mm thick reeded glass fixed with wooden beading of size 10mm wide flushed to the thickness of the frame including cost of materials, labour charges, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34, 9.42 and as directed by the Engineer in Charge of the work.	Sqm	2380.00	Rupees Two Thousand Three Hundred Eighty Only
26	2.00	KSRB 9-27.1 : Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications Fixing of door frame and as directed by the Engineer in Charge of the work.	No	969.00	Rupees Nine Hundred Sixty Nine Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

Scanned by CamScanner

	Qty	Item Description	Unit	Rate	
				In Figures	In Words
	2	3	4	5	6
	9.00	Fixing of window frame	No	657.00	Rupees Six Hundred Fifty Seven Only
	2.00	Fixing of ventilator frame	No	500.00	Rupees Five Hundred Only
29	9.81	Providing and fixing Stainless steel staircase raling as per Chief Architect Drawing No. 11520/ HRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges, etc., complete as per specifications and as directed by the Engineer in Charge of the work.	Sqm	6566.00	Rupees Six Thousand Five Hundred Sixty Six Only
30	125.00	Concealed conduit System: Supplying ..... mm dia 2mm2. 5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/ PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement roda by using biniding wires and unused ways of junction boxes and pipe ends should be coverd using PVC end enclosures. run with 18SWG GI. fish wire whereever necessary. 25mm dia 2mm thick	Per Mtr	43.00	Rupees Forty Three Only
31	135.00	Groove cutting: Supplying.....dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, meatal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run through our the conduit wherever necessary.. 25mm dia 2mm thick	Per Mtr	56.00	Rupees Fifty Six Only
32	10.00	Supplying and mounting teak wooden box without front plank made out of not less than 12 mm thick wood after due groove cutting necessery masonary patch work complete.12x9x3 (300x228x76mmx0	Per Mtr	84.00	Rupees Eighty Four Only
33	40.00	Supplying and mounting teak wooden box without front plank made out of not less than 12 mm thick wood after due groove cutting necessery masonary patch work complete.10x7x3 (254x178x76mm)	Per Mtr	71.00	Rupees Seventy One Only
34	6.00	Supplying and mounting teak wooden box without front plank made out of not less than 12 mm thick wood after due groove cutting necessery masonary patch work complete. 8x6x3 (203x152x76mm)	Per Mtr	55.00	Rupees Fifty Five Only
35	8.00	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the exisiting plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. Short poiknt upto 3Mtr from tapping point to our let via switch	Point	184.00	Rupees One Hundred Eighty Four Only
36	12.00	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the exisiting plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. Medium kpoint above 3Mtr uupto 6Mtr frolm tapping point to out let via switch	Point	273.00	Rupees Two Hundred Seventy Three Only
37	20.00	Point wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the exisiting plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. Long point above ^Mtr from tapping point to out let via switch	Point	386.00	Rupees Three Hundred Eighty Six Only
38	12.00	Supplying 6A flush/projected type socket and a 6amps flush/projected type SP switch either surface/flush mounting in a existing gang box or in a 4mm thick plastic sheet and fixing oure a flush mounted wooden box and wiring using necessary capacity wires as required. 6Amps 3/5 Way	Each	111.00	Rupees One Hundred Eleven Only
39	5.00	Supply and fixing of backlite D.P/Socket/switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches. 32Amps Flush/projecte type DP switch	Each	152.00	Rupees One Hundred Fifty Two Only
40	5.00	Supply and fixing of backlite D.P/Socket/switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches. 16Amps Flush type Univerals socket	Each	100.00	Rupees One Hundred Only
41	150.00	Wiring for lighting/power circuit using one of PVC insulated 11oov grad, multis and copper conductor single core cable in open or consealed system of wiring. I Group A Materials 1.5 sqmm	Per Mtr.	16.00	Rupees Sixteen Only
42	200.00	Wiring for lighting/power circuit using one of PVC insulated 11oov grad, multis and copper conductor single core cable in open or consealed system of wiring. I Group A Materials. 2.5 sqmm	Per Mtr.	26.00	Rupees Twenty Six Only
43	150.00	Wiring for lighting/power circuit using one of PVC insulated 11oov grad, multis and copper conductor single core cable in open or consealed system of wiring. I Group A Materials. 4 sqmm	Per Mtr.	34.00	Rupees Thirty Four Only
44	125.00	Wiring for lighting/power circuit using one of PVC insulated 11oov grad, multis and copper conductor single core cable in open or consealed system of wiring. I Group A Materials. 6 sqmm	Per Mtr.	55.00	Rupees Fifty Five Only
45	8960.00	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulators etc., and fixing on existing wooden or meatl box using N.F. screws.	SqCm	0.25	Rupees and Paise Twenty Five Only
46	10.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes or size.... mm conduit using necessary machine screws. 80mm	No	8.00	Rupees Eight Only
47	6.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes or size.... mm conduit using necessary machine screws. 110mm	No	9.00	Rupees Nine Only
48	6.00	Supplying and fixing metal fan box with round hook	Each	76.00	Rupees Seventy Six Only
49	25.00	Supplying and fixing PBBC bakelitelite straight or slant batten holder and wiring, within 60w/230 Volts lamps Group 'A'	Each	63.00	Rupees Sixty Three Only
50	2.00	Supplying and fixing cast Aluminium round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp as required Group ' A '	Each	1153.00	Rupees One Thousand One Hundred Fifty Three Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

discrepancy please inform the Competent Authority.

Scanned by CamScanner

		Item Description	Unit	Rate	
				In Figures	In Words
		3	4	5	6
	10.00	Supply box type fluorescent tube light fitting of 4'- 36/40 watts fluorescent tube fitting, made out of M.S sheet and stove enameled with low loss open construcion copper woundferromagnetic ballast, starter locking type brass contact holders mounted on double fold type sheet base fully wited for use on 230 Volts A.C Supply including fluorescent tube. 1 1x4'-36/40Watts	Each	709.00	Rupees Seven Hundred Nine Only
52	4.00	Supplying of 1440rpm heavy duty eahust fan with bracket blades suitable for operate on 230V 50Hz. AC Supply complete. 1 12" Sweep (300mm)	Each	2625.00	Rupees Two Thousand Six Hundred Twenty Five Only
53	8.00	Supplying capactor type ceiling fan cpmplet with down rod blades, shackele, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 48" Sweep (1200mm) Regular model (Khaitan, Crompton Greaves, Orient, Polar, Bajaj, Usha, Havells, Almonard)	Each	1890.00	Rupees One Thousand Eight Hundred Ninety Only
54	4.00	Fixing all types and all capacities fluorescent/false ceiling/spot light/ CGL fittings indoor on the wall/ ceiling/ rafters/ girders using 23/ 0.0076" twin twisted PVC insulated wires, required nos of round blocks and clamps (if required) On wall/ceiling/Rafter/Girders	Each	110.00	Rupees One Hundred Ten Only
55	8.00	Fixing a ceiling/Wall mounting fan of all capacities and all types to the existing S hook together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire and wiring completely.	Each	110.00	Rupees One Hundred Ten Only
56	4.00	Fixing one exhaust fan in the nitch already left in the wall with bolts and nuts and 5 amps ceiling rose with suficient length of 23/ 0.0076 inch PVC insulated twin core wire of approved make.	Each	326.00	Rupees Three Hundred Twenty Six Only
57	1.00	Supply and fixing ploished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tappered invrted wooden plugs screws etc. 20"x20"x2.5"	Each	299.00	Rupees Two Hundred Ninety Nine Only
58	1.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., Complete. 32A mps	Each	105.00	Rupees One Hundred Five Only
59	4.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring cdomplete as required. A) 5-32Amps	Each	205.00	Rupees Two Hundred Five Only
60	1.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring cdomplete as required. D) 40-63Amps DP	Each	856.00	Rupees Eight Hundred Fifty Six Only
61	1.00	Supplying and fixing regular MCB disrtibution boards on wall/woodboard / flush mounting using required calmps, boltd, nuts etc., with provision for fixing suitable type capacdity MCB's single phase / 3 phase / single door with powder coated painting etc., complete II - Double Door B) 8 Way SP & N	Each	1355.00	Rupees One Thousand Three Hundred Fifty Five Only
62	1.00	Supplying, fixing and wiring earth leakage Miniature Circuit Breaker (ELMCB) 240/450 v up to 300mA sensitivity on existing wood / Panel Board. 32-40 Amps 2 pole	Each	2273.00	Rupees Two Thousand Two Hundred Seventy Three Only
63	1.00	Supplying and fixing one of 230 volts Ding dong bell and a flush type bell push with gang box fixed on necessary wooden or rawl plugs using NF screws.	Each	192.00	Rupees One Hundred Ninety Two Only
64	1.00	KSRB 11-5 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Each	5406.00	Rupees Five Thousand Four Hundred Six Only
65	1.00	KELE SRB 11-11.3 : Providing and fixing white vitreous china clay, flat back wash basin size 550x400mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Each	2479.00	Rupees Two Thousand Four Hundred Seventy Nine Only
66	1.00	KELE SRB 11-17-2 : Providing and fixing C.P. brass towel rail 600 mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications.	Each	737.00	Rupees Seven Hundred Thirty Seven Only
67	1.00	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot) Of size 10cms x 7.5cms	Each	278.00	Rupees Two Hundred Seventy Eight Only
68	15.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) 20mm nominal OD pipes	Mtr	223.00	Rupees Two Hundred Twenty Three Only

Signature of Contractor

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

Scanned by CamScanner